No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
5	Draft and approach clearing and using the earth for improving the flank bund at the right side of the weir	L. S.	..	..	
6	Providing a piped vent of 6" dia. at the centre of the weir at R. L. 49·00	"	..	..	
	Sluice at C.S. 9 at R.L. 49.00.				
1	Earthwork cutting open the bund and refilling with watering consolidation	C.yd.	0 3 6	64	
2	Concrete in cement mortar 1 : 5 : 10	C.ft.	0 6 0	188	
3	Cut laterite in cement mortar	"	0 6 0	149	
4	Burnt stone slabs 4½" to 6" thick dressed and fixed in mortar	S.ft.	1 0 0	26	
5	Cutting holes in slabs	Each	1 0 0	3	
6	Providing plug with iron rod with locking arrangement, etc.	"	10 0 0	1	
7	New laterite stone revetment work with 1 mile lead.	C.yd.	2 8 0	16	
8	Providing 6" dia. C.I. pipe including carting and fixing with cement joints at junction	R.ft.	3 8 0	30	

P. SUBBA RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 11th July 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 6th August 1938, for Protective works to Kallahalli Tank, Reg. No. 22 of Chitaldrug Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 180 (one hundred and eighty only) which should be credited to the Treasury and the Treasury Challan enclosed as earnest money and be superscribed "Tender for Protective works to Kallahalli Tank, Reg. No. 22, Chitaldrug Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of quantities required for the Protective Works of Kallahalli Tank, Register No. 22 of Chitaldrug Taluk.

Sl. No.	Items of work	Per	Rate	Quantity	Tendered rates in	
					Words	Figures
	Constructing a relieving weir 80′ *gap (breached)* 61·50 *R.L.*		Rs. a. p.			
1	Earthwork excavation	C.yd.	0 3 0	71		
2	Size stone in surki mortar	C.ft.	0 5 0	863		
3	Cement concrete 1 : 2½ : 5	,,	0 10 0	47		
4	Rough stone work	C.yd.	1 8 0	80		
5	Cement pointing	Sqr.	4 0 0	1·80		
6	Sundry and unforeseen works	L. S.	Rs. 2	..		
	Closing the breach.					
1	Removing the temporary bund and clearing site, etc.	L. S.	Rs. 100			
2	Excavating foundation for core wall in soft rock	C.yd.	0 6 0	46		
3	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	250		
4	Size stone in cement mortar 1 : 6 ..	,,	0 6 0	947		
5	Earthwork to bund including lead, watering, etc.	C.yd.	0 5 0	779		
6	Rough stone revetment	,,	1 8 0	148		
7	Gravel backing	,,	0 8 0	60		
8	Turfing the slopes	S.yd.	0 1 0	342		
9	Sundry and unforeseen works	L. S.	Rs. 49			
	Lowering the weir to 60·00 *for a length of* 218′.					
1	Earthwork excavation in hard gravel mixed with boulders using the same for training bank	C.yd.	0 6 0	5,581		
2	Sundry and unforeseen works	L. S.	Rs. 7.			

K. SUBBA RAO,
For *Executive Engineer.*

MISCELLANEOUS DEPARTMENTS

IN THE HIGH COURT OF MYSORE AT BANGALORE.

R. O. C. No. 2—38-39.

Notice dated 1st July 1938.

Tenders are invited for printing the records of the High Court in selected appeals, etc., for a period of two years with effect from the 1st November 1938.

2. Tenders which must only be in the prescribed form appended to this notice should be sent in a sealed cover superscribed "Tenders for Printing Records," and should be addressed to the Registrar, High Court of Mysore, Public Office Buildings, Cubbon Park, Bangalore.

3. Tenders will be received up to 12 NOON on Thursday the 29th September 1938 and will be opened by the Registrar in the presence of such of the tenderers as may attend.

4. Every tender should be accompanied by a deposit of Rs. 50 in currency notes.

5. The name or names of successful tenderer or tenderers will be put up on the Notice Board of the High Court and no further enquiries regarding acceptance or rejection of tenders will be attended to.

6. The successful tenderer or tenderers shall, within one week from the date of acceptance of their tender or tenders, execute a stamped agreement, and also deposit a sum of Rs. 150 in cash or in Government Promissory Notes (less the initial deposit of Rs. 50) for the due performance of the contract. The deposits of the unsuccessful tenderers will be returned to them.

7. The Registrar does not bind himself to accept the lowest or any tender, or to accept or reject more than one tender without assigning any reasons.

8. The printing shall be done on durable white paper of foolscap size in clear type expeditiously and correctly and in all respects to the satisfaction of the Registrar. Kannada types should be used where such words are found.